

Milestone 2

Team 50

Software Engineering Project: Jan-Setu



Team Members

Name	Email
Tushar Sharma	21f3000007@ds.study.iitm.ac.in
Amit Kumar Gupta	21f1005763@ds.study.iitm.ac.in
Sarthak Kumar Tiwari	23f3000340@ds.study.iitm.ac.in
Parkhi Yadav	22f3002870@ds.study.iitm.ac.in
Veer Vikram Singh	23f3000375@ds.study.iitm.ac.in

Component Design

1. Overview


Jan Setu accepts civic complaints through a React web portal and Meta WhatsApp, then runs both channels through one FastAPI/PostgreSQL pipeline. The pipeline validates intake, transcribes voice, classifies and routes complaints, checks optional photo evidence, aggregates eligible duplicates, dispatches cases, and stores an auditable status history for citizens and officials.

Implemented core identifies functionality present in the codebase. It does not assert every Milestone response-time target without operational measurement.

ID	Story	Status	Primary components
US 01	WhatsApp-linked registration	Implemented core	Login, Auth Module, WhatsApp webhook/client, Auth Context
US 02	Voice-note filing	Implemented core	Conversation Engine, STT Service, Voice Recorder
US 03	Location-based routing	Implemented core	Location Picker, Geocoder, Classifier, Taxonomy
US 04	Image-text verification	Implemented core	Photo Upload, Media Service, vision classifier, Official Console
US 05	Short-term/long-term classification	Implemented core	Classifier, taxonomy, Review Card, Official Console
US 06	Non-priority aggregation	Implemented core	Dedup Engine, Worker, grievance/job repositories
US 07	Immediate priority filing	Implemented core	Taxonomy policy, Orchestrator, Dispatch Adapter
US 08	Web status tracking	Implemented core	Dashboard, Detail page, Timeline, grievance events
US 09	WhatsApp status request	Implemented core	Webhook, Conversation Processor, Outbound Dispatcher
US 10	Structured intake on both channels	Implemented core	Filing Wizard, API Schemas, persisted WhatsApp FSM

2. System Architecture

Stories: **US 01 US 10.** Web and WhatsApp use the same API, persistence layer, and durable pipeline; only their intake adapters differ.



3. Component Traceability

3.1 Interfaces and Application Services

Components	Responsibility	Stories
App Router, Public Shell, Landing, About	Public navigation and entry points.	Cross-cutting. Implemented product pages; not standalone Milestone acceptance items.
Login, Auth Context, API Client	Reverse-OTP sign-in, in-memory JWT, httpOnly refresh restoration.	US 01
Filing Wizard, Location Picker, Voice Recorder, Photo Upload, Review Card	Collect and validate evidence; show enriched review before confirmation.	US 02, US 03, US 04, US 05, US 07, US 10
Dashboard, Complaint Detail, Status Chip/Timeline	List complaints, render status/event history, download available receipt.	US 08; shared data supports US 09
Language Picker, I18n Context	Six implemented catalogs: English, Hindi, Bengali, Marathi, Telugu, Tamil.	US 01, US 02, US 08, US 09, US 10
Official Login, Official Console, Official API	Department-scoped queue, live metrics, evidence/routing review, approve/redirect/reject/clarify actions.	US 04, US 07
WhatsApp Webhook, Client, Conversation Engine, Processor	Verify inbound events, drive persisted dialogs, emit outbound messages.	US 01, US 02, US 09, US 10
App Factory, Configuration, Error Boundary, rate limits	Safe application setup, recovery, and provider protection.	Cross-cutting

3.2 Pipeline, Data, and Operations

Components	Responsibility	Stories
Pipeline Orchestrator, Background Worker	Run/recover enrichment, confirmation, aggregation-window expiry, and dispatch work.	US 02, US 09
STT Service	Sarvam transcription with text-only degradation.	US 02
LLM Classifier, Image Match Checker	Extract category, department, priority, term, facts, and image consistency.	US 03, US 04, US 05, US 07
Geocoding Service, Taxonomy Registry	Resolve address and apply jurisdiction, SLA, department, priority, and routing policy.	US 03, US 07
Dedup Engine	Join nearby, same-category, non-priority reports during configured window.	US 06

Components	Responsibility	Stories
Media Service, PDF Generator	Store evidence; generate Unicode PDF for web download and WhatsApp confirmation.	US 02, US 04, US 08
Dispatch Adapters	Implemented SMTP and mock municipal API dispatch.	US 06, US 07
Models, Repository Layer, PostgreSQL, file storage	Persist identities, conversations, grievances, events, jobs, routing, and audit records.	Cross-cutting

4. Frontend Architecture

4.1 Component Hierarchy

Stories: US 01, US 03, US 04, US 08, US 10. Public and authenticated routes separate identity, filing, tracking, and official review.

4.2 Authentication State — US-01


Access token stays in memory. Page refresh uses `/auth/refresh` with an httpOnly refresh cookie.

4.3 Reverse-OTP Login — US-01

Web displays a code and deep link; citizen approves via WhatsApp or sends the displayed fallback code.

4.4 Filing Wizard — US-02, US-03, US-04, US-10

The four-step wizard holds local state until a single multipart submission. Location and issue are mandatory; audio and photo are optional evidence.



4.5 Localisation and Accessibility

Six typed UI catalogs are implemented. Source-language evidence, transcripts, addresses, and ticket IDs remain unchanged. Hindi/English are available in the WhatsApp-facing flows; other UI catalogs expand web inclusion.

5. Backend and Processing Architecture

5.1 Application Layer and API Surface

Stories: US 01 US 10. FastAPI handles ingress, keeps authoritative state, and leaves durable external work to the worker.

API group	Routes	Stories
WhatsApp	<code>GET/POST /whatsapp/webhook</code>	US 01, US 02, US 09, US 10
Citizen auth	<code>/auth/request-code</code> , <code>/auth/status</code> , <code>/auth/refresh</code> , <code>/auth/logout</code>	US 01
Citizen grievances	<code>/api/grievances</code> plus detail, edit, confirm, cancel, PDF, audio, transcription-preview routes	US 02, US 03, US 04, US 08, US 10
Official portal	official login and department-scoped queue/detail/action routes	US 04 US 08

5.2 Webhook Durability — US-01, US-02, US-09, US-10

Meta events are HMAC-verified, stored, acknowledged immediately, then processed asynchronously. Worker sweeps recover unprocessed events.

5.3 Token Architecture — US-01

15-minute JWT is memory-only. Opaque 30-day refresh token is hashed in storage; six-character verification code expires after 10 minutes.

5.4 Conversation FSM — US-02, US-09, US-10

Persisted state, optimistic concurrency, outbound persistence, 24-hour service-window handling, and seven-day conversation TTL make WhatsApp filing recoverable. A standalone `status` or `फ़िल` message with no active conversation returns recent complaints.

5.5 Shared Pipeline — US-02–US-07

Every stage degrades rather than loses a complaint: STT continues with text, classification becomes `uncategorized`, geocoding/image/PDF failures are flagged, and dispatch retries.

Stage	Stories	Degradation
STT	US 02	Continue with available text.

Stage	Stories	Degradation
Classification / term / priority	US 03, US 05, US 07	Provider fallback; default category.
Geocoding	US 03	Preserve coordinates if address resolution fails.
Image matching	US 04	Flag or skip; never auto-reject.
Deduplication	US 06	Priority cases bypass aggregation.
Dispatch	US 06, US 07	Retry with backoff; retain failed state.

5.6 Classification and Routing — US-03, US-04, US-05, US-07
Groq provides primary structured extraction; OpenRouter is fallback and vision path. Output contains category, department, priority, resolution term, safety, confidence, and facts. Taxonomy then applies jurisdiction and routing policy.

5.7 Repository Layer and Worker
Repositories split identity, messaging, grievances, routing, officials, and events while preserving a unified import surface. Worker claims jobs with optimistic locking, sends pending replies, expires aggregation windows, and retries dispatch.

6. Data, Integrations, and Deployment

6.1 Domain Model

Stories: US 01 US 10. grievance_events drive web timelines and WhatsApp status results; official audit events preserve decisions.

Context	Role	Stories
Citizen Identity	Contacts, accounts, verification, refresh tokens	US 01
Messaging	Conversations, WhatsApp messages, consumption, webhooks	US 01, US 02, US 09, US 10
Grievance Management	Complaints, events, extraction, jobs, dispatch outbox	US 02 US 09
Jurisdiction	Geographies and routes	US 03, US 07
Official Portal	Official identity and audit trail	US 04 US 07
Utility / Cache	Geocoder cache and provider throttling	Cross-cutting

6.2 External Integrations

All provider calls use timeouts, throttling, and graceful degradation. Public Nominatim is limited to development traffic.

Integration	Stories
Meta Cloud API	US 01, US 02, US 09, US 10
Sar vam	US 02
Groq / OpenRouter	US 03, US 04, US 05, US 07
Nominatim / OSM	US 03
SMTP / mock municipal API	US 06, US 07

6.3 Deployment

Development uses host-reloaded API/Vite with containerised PostgreSQL, worker, Mailpit, and tunnel. Production-like Compose runs Nginx SPA, API, worker, PostgreSQL, shared uploads, and Mailpit.

Development

Production


7. End-to-End Flows

7.1 Web Filing — US-03–US-08, US-10

Validated intake becomes a draft, is enriched, reviewed, confirmed, routed or aggregated, dispatched, and then tracked through complaint events.

7.2 WhatsApp Filing — US-02, US-03, US-09, US-10

Conversation collects location, issue, and optional photo; the same pipeline returns a confirmation-ready ticket. A later status / रिपोर्ट query retrieves recent complaint states.



8. Security, Inclusion, and Planned Extensions

8.1 Security and Inclusion

Area	Implemented control	Stories
Webhook	HMAC SHA256 verification and idempotent event processing	US 01, US 02, US 09, US 10
Citizen auth	Reverse OTP, memory-only JWT, hashed httpOnly refresh token	US 01
Official access	Email OTP, department scope, action audit trail	US 04 US 08
Accessibility	WCAG 2.2 AA target, semantic markup, keyboard focus, large touch controls, zoom/reduced-motion support, non-colour status meaning	US 01, US 02, US 08, US 10
Language	English/Hindi WhatsApp copy; six implemented web UI catalogs	US 01, US 02, US 08, US 09, US 10

8.2 Verified Planned Extensions


Extension	Reason
Real municipal department adapters	Current SMTP and API adapters are explicitly demo implementations; protocol supports replacement.
Production geocoder and managed hosting	Public Nominatim is development-only; Compose production profile is a local production-like deployment.
Status-change push notifications and seven-day inactivity escalation	Timeline/status retrieval exists, but codebase does not evidence these US 08 acceptance behaviours.
Natural-language WhatsApp status intent, resolved-action summary, and measured 30 second response target	Current implementation recognises only status / स्थिति and returns recent status lines.
Measured response-time SLAs	Architecture supports processing, but no operational measurements substantiate Milestone timing claims.

Traceability: Every Milestone story maps to implemented components. Planned extensions are limited to functionality not present or not evidenced by the current codebase; implemented locales, public pages, PDF receipts, and official metrics are intentionally excluded from future scope.

Database Design diagram


Jan-Setu

Database Entity-Relationship Diagram
18 + 3 Tables - PostgreSQL - SQLAlchemy ORM



Link to Database Schema: [Click Here](#)
(Download it from there for better view)
[Confluence Link](#)

Class Diagram



Link to Class Diagram for Better
view: [Click Here](#)
[Confluence Link](#)

Sprint Schedule

3.1 How We Work: Agile Framework & Team Rhythm

To keep our momentum steady and stay aligned across design, frontend, backend, and QA, we work in 2-week sprint cycles (condensed to 10-day sprints during build-heavy phases). Here is our regular routine:

- **Sprint Planning:** On the first day of every sprint, we review our backlog, set our primary goal, estimate effort in Jira, and assign task ownership.
- **Standups / Sync Meetings:** Every Monday, Wednesday, and Friday, we meet briefly to share progress, clear blockers, and keep our Kanban board up to date.
- **Sprint Review & Client Demo:** In client meetings we demo working features to our stakeholders (Balasurya K & Sonika Pal) to gather early, actionable feedback.
- **Sprint Retrospective:** Right after the demo, we reflect on how we worked together, pinpoint bottlenecks, and tweak our processes for the sprint submission and for next cycles.

3.2 Sprint Schedule & Roadmap (Sprint 1 – Sprint 5)

Sprint & Milestone	Date Range	Sprint Goal	Modules & Focus Areas	Team Ownership	Key Deliverables & Outputs
Milestone 1	12 June – 28 June 2026	Uncovering user needs, selecting our domain & gathering requirements	Stakeholder mapping, discovering pain points, writing SMART user stories	• All Members: Draft questionnaire, run interviews, log proof. • Amit & Tushar: Define problem domain & user roles. • Veer, Parkhi, Sarthak: Write initial SMART stories.	• M1 PDF Report • Audio/Video interview recordings • User profiles (Primary, Secondary, Tertiary) • SMART User Stories
Milestone 2	29 June – 23 July 2026	Designing architecture, UI/UX prototyping & plotting project schedule	Component design, database schema, class diagrams, frontend UI mockups	• Veer: Frontend wireframes & core pages (Landing, Login). • Parkhi: Dashboard & complaint filing flow. • Tushar: ER diagram, DB schema, SRS document. • Sarthak: Software Test Plan (STP), Gantt/Kanban setup. • Amit: PRD, SAD lead, Scrum notes.	• Milestone 2 PDF Report • Frontend HTML/CSS/JS ZIP + README • Database Schema & Class Diagram • Gantt Chart & Kanban screenshots • team-050-milestone-1-2.zip
(Milestone 3 / Sprint 1)	24 July – 02 August 2026	Building core APIs, OpenAPI specs & setting up Pytest	User authentication, complaint filing, role-based access control APIs	• Tushar: Core REST API endpoints (Flask) & DB ORM. • Amit: Swagger-compatible YAML spec & story mapping. • Sarthak: Pytest unit test suite & test runner setup. • Veer & Parkhi: Prep frontend for API integration.	• Swagger/OpenAPI YAML file • Functional Backend REST API code • Automated Pytest suite & test reports • User feedback log & Sprint 4 plan
(Milestone 4 / Sprint 2)	03 August – 12 August 2026	Plugging in GenAI, advanced workflows & full-stack integration	AI complaint triage/summaries, workflow tracking, frontend-backend hookup	• Parkhi & Amit: GenAI / LLM API integration (OpenAI / Gemini / LangChain) for auto-tagging. • Veer & Parkhi: Wire up Vue.js/JS frontend to backend. • Tushar: Complex queries & notification APIs. • Sarthak: End-to-end API test suite & edge-case checks.	• Working GenAI API pipeline • Connected full-stack prototype • Expanded Pytest test suite & results • End-user feedback & validation report
(Milestone 5 / Final Submission)	13 August – 23 August 2026	System testing, issue tracking, video demo & packaging	End-to-end verification, bug squashing, documentation & presentation	• Sarthak: Pre-commit hooks, CI/CD pipeline check & code audit. • Amit & Tushar: Issue tracking docs & GitHub PR review summaries. • Veer & Parkhi: Demo video, slides & setup guides. • All Members: Compile final PDF report & package project.	• Complete application source code ZIP • Final consolidated PDF report • Video demo & presentation deck • Setup README (Ubuntu/Mac/Win) • team-050-milestone-3-5.zip

3.3 Detailed Sprint Breakdown

Sprint 1 (12 June – 28 June 2026): Requirement Analysis & User Discovery

- **Focus:** Nailing down our problem statement, talking to users, and writing user stories.
- **Key Tasks:**
 - Defined our user roles: Citizens (Primary), Local Authorities/Admins (Secondary), and System Auditors (Tertiary).
 - Conducted user research interviews (logging audio/video recordings) to understand genuine day-to-day problems rather than forcing pre-planned features.
 - Translated user feedback into SMART (Specific, Measurable, Achievable, Relevant, Time-bound) user stories.

Sprint 2 (29 June – 23 July 2026): System Architecture, Design & UI Prototyping

- **Focus:** Mapping out system components, building responsive web pages, designing the database, and setting project timelines.
- **Key Tasks:**
 - Created UI wireframes and functional pages (Landing Page, Login/Signup, User Dashboard, and Complaint Registration Flow).
 - Designed our relational Database Schema (ER Diagram) and UML Class Diagrams.
 - Drafted foundational documentation: Software Requirements Specification (SRS), Architecture Document (SAD), and Software Test Plan (STP).
 - Bundled all initial deliverables into team-050-milestone-1-2.zip following course validity guidelines.

Sprint 3 / Milestone 3 (24 July – 02 August 2026): Core API Development & Testing

- **Focus:** Building scalable backend endpoints, generating OpenAPI documentation, and writing unit tests.
- **Key Tasks:**
 - Built foundational REST API endpoints using Flask for User Authentication, Profile Management, and Complaint Submissions.
 - Wrote a Swagger-compatible YAML specification detailing request/response models, status codes, and user story links.
 - Set up an automated test suite with Pytest to validate business logic and handle error paths cleanly.
 - Ran early user testing sessions to get initial feedback on core workflows.

Sprint 4 / Milestone 4 (03 August – 12 August 2026): GenAI Pipeline & Full-Stack Integration

- **Focus:** Connecting GenAI for smart complaint routing, wiring the frontend to backend APIs, and executing full integration tests.
- **Key Tasks:**
 - Integrated LLM APIs (OpenAI / Gemini / LangChain) to automatically summarize complaints and tag the appropriate departments.
 - Hooked up our Vue.js/JavaScript frontend components directly to backend REST endpoints.

- Expanded our test coverage to catch third-party API errors and unusual user input edge cases.
- Collected structured user feedback to fix navigation flow and improve UI responsiveness.

Sprint 5 / Milestone 5 (13 August – 23 August 2026): Code Review, Issue Tracking & Final Showcase

- **Focus:** Cleaning up code, documenting issue tracking, recording the demo, and packaging final deliverables.
- **Key Tasks:**
 - Documented our GitHub issue history, PR reviews, and bug resolution logs with screenshots.
 - Wrote clear, step-by-step setup guides (README.md) for Windows, macOS, and Ubuntu environments.
 - Recorded a walk-through video showcasing the complete end-to-end working app.
 - Compiled the final PDF report and verified team-050-milestone-3-5.zip using the course Validity Tool.

Scrum Meetings Schedule and Minutes

1. Scrum Meetings Schedule

- Standard Scrum Meetings: Held every Monday.
- Sprint Planning & Coordination: Held on alternate days throughout the week.

2. Scrum Meeting Minutes

1. 25 June 2026 [Link](#)

- Meeting Focus: Project Discussion & Requirements
- Attendees: Amit, Tushar, Veer, Parkhi, Sarthak
- Key Discussions & Decisions: Identified primary/secondary/tertiary users. Prepared user interview questionnaire and assigned interview responsibilities to all members.

2. 04 July 2026 [Link](#)

- Meeting Focus: Wireframe, Task Ownership & Tech Stack
- Attendees: Amit, Tushar, Veer, Parkhi, Sarthak
- Key Discussions & Decisions: Reviewed Web Application UI Wireframe. Assigned documentation ownership: STP to Sarthak, SAD to Veer, SRS to Tushar, and PRD to Amit. Discussed project tech stack.

3. 12 July 2026 [Link](#)

- Meeting Focus: Client Progress Review
- Attendees: Team + Balasurya K (Client) & Sonika Pal (Researcher)
- Key Discussions & Decisions: Conducted progress demos for the clients. Client approved of the progress and requested the addition of an ER Diagram / Database Schema, which was assigned to Tushar.

15 July 2026 [Link](#)

- Meeting Focus: Sprint 3 Planning & Ticket Assignment
- Attendees: Amit, Tushar, Veer, Parkhi, Sarthak
- Key Discussions & Decisions: Closed out Sprint 2 and initiated Sprint 3. Created ticket JSA-10 to track Milestone 2 deliverables. Assigned new development and research tickets for the upcoming sprint.

3. Sprint Schedule

Sprint 2 (Concluded 15 July 2026: Milestone 2 basic changes continues)

- Focus & Goals: Web Application UI Wireframes, initial tech stack planning, and documentation (STP, SAD, SRS, PRD).

Sprint 3 (15 July 2026 – 29 July 2026)


- Frontend: Veer to build Landing & Login pages and final wireframe draft. Parkhi to build Dashboard and Complaint Registration flow.
- Backend / Database: Tushar to create the Database Schema, ER Diagram, and integrated APIs YAML file.
- Research & Pipeline: Sarthak to research pre-commit hooks and CI testing pipeline. Amit to research open-source APIs. Parkhi to research LLMs for the AI pipeline.

Gantt Chart


Jan Setu

Smart Complaint Triage & Routing System — Project Timeline

MAY2026-Team-050
Prepared by Parkhi Yadav, Scrum Master




Kanban Board



Screenshots of the Frontend Pages

About Page



Common complaints, routed to the right department

Every category maps to a real municipal department — no report goes to a generic inbox.

Roads & Potholes Public Works Department	Street Lighting Electrical Department
Sanitation & Public Toilets Sanitation Department	Drainage & Sewerage Public Works Department
Water Supply Water Works Department	Garbage Collection Sanitation Department
Stray Animal Cruelty & Care Animal Welfare Department Priority — skips grouping	Parks & Public Spaces Parks & Gardens Department
Encroachment Town Planning Department	Electricity Electrical Department
Other General Grievance Cell	

Verified by WhatsApp, not a password

Signing in is approved from your own WhatsApp number — nothing to remember, nothing stored but your phone number and reports.

Citizen Sign in Page

Official access →

How Jan Setu works →

Citizen grievance portal

WhatsApp → routed ticket → visible updates

Approve securely. Track visibly.

Existing users approve sign-in in WhatsApp. New users verify once with a secure code.

Citizen sign in

Use your WhatsApp number

If your account is already linked, Jan Setu sends a WhatsApp notification. Tap Yes to approve this browser—no code to type.

WhatsApp phone number

+91 98765 43210

Use the number linked to your Jan Setu WhatsApp account.

1 Enter your number

2 Approve on WhatsApp

3 Dashboard opens

Continue securely →

We never ask you to share a WhatsApp OTP with another person.

Jan Setu

Citizen grievance portal

Dashboard

New complaint

About Jan Setu

English

Log out

Citizen dashboard

New complaint

Your complaints

Every report, visible from registration to department action.

TICKET ID	CATEGORY	STATUS	FILED ON
JS-DEMO-10001	P Pothole surface damage Priority	Registered	18 Jul 2026
JS-DEMO-10002	O Open or damaged manhole Priority	Awaiting confirmation	20 Jul 2026
JS-DEMO-10003	S Streetlight out Normal priority	Registered	23 Jul 2026

Restricted government access

Official operations

Sign in with a pre-approved government email.
Access and evidence views are audited.

Official email

demo-official@example.com

Send one-time code

Officials Login Page

Officials Dashboard

Government operations - cedar-grove-demo

Civic triage desk

Morgan Hale - Civic Operations Supervisor

Sign out

Visible cases2

Needs review2

Immediate safety1

A2 unavailable0

Dispatch failed0

Triage queue

JS-DEMO-10001

Pothole or road surface damage

42 Willow Lane, Cedar Grove

Selected ✓

pending_official

JS-DEMO-10002

Open or damaged manhole

8 Market Street, Cedar Grove

Safety

JS-DEMO-10001

Pothole or road surface damage

18/7/2026, 3:00:00 pm

Status

pending_official

Disposition

municipal ticket

Location

42 Willow Lane, Cedar Grove

Original complaint

Deep pothole beside the school bus stop is dangerous for bicycles and scooters.

Normalized summary

Deep pothole beside a school bus stop creates a hazard for people cycling and riding scooters.

Automation evidence and routing

Required decision note

Explain evidence and policy basis...

Approve route

Ask citizen

Redirect

Reject

Department

public_works

Confidence

94%



Jan Setu
 Citizen grievance portal

Dashboard
 New complaint
 About Jan Setu

English
 Log out

STEP 1 OF 4
Choose location

1 Location 2 Details 3 Photo 4 Review



No location selected yet. Use your location or tap the map to place the pin.

Nearby landmark (optional)

e.g., opposite the water tank, near the primary school

Continue →

Use my location

Pin the exact place

Use your current location, tap the map, or drag the pin. A precise location helps the right team find the issue without calling you for directions.

Location is attached only to this complaint.

New Complaint : Step-1 Page


Jan Setu
 Citizen grievance portal

Dashboard
 New complaint
 About Jan Setu

English
 Log out

STEP 2 OF 4
Describe the issue

1 Location 2 Details 3 Photo 4 Review

What happened? Include a nearby landmark, how long the problem has existed, and any safety risk.

0/2000 characters - or add a voice note

Record voice note

00:00/01:00

Maximum 60 seconds - recording stops automatically when time is up.

Tell it in your own words

Type or record a voice note. Mention what is broken, when you noticed it, and whether anyone is at immediate risk.

You need either text or one voice note.

Back Continue →

New Complaint : Step-2 Page


Jan Setu
 Citizen grievance portal

Dashboard
 New complaint
 About Jan Setu

English
 Log out

STEP 3 OF 4
 Add a photo

Location
 Details
 Photo
 Review


Help the department see the issue
 A clear, well-lit photo is optional. Avoid faces, number plates, or unrelated personal information.


Add a clear photo
 Take a photo or choose JPEG, PNG, or WebP - maximum 5 MiB
 Choose photo

Continue without a photo

Back

New Complaint : Step-3 Page


Jan Setu
 Citizen grievance portal

Dashboard
 New complaint
 About Jan Setu

English
 Log out

STEP 4 OF 4
 Review & submit

Location
 Details
 Photo
 Review

Final check
Review what we understood
 Confirm the facts—not the bureaucracy. Department, urgency, and routing are determined from reviewed policy.

Ticket ID JS-DEMO-10003	Issue Streetlight not working
Service area Public Lighting	Proposed owner Cedar Grove Municipal Services
Handling municipal ticket	
Location 17 Maple Avenue, Cedar Grove	
Issue summary Streetlight outside the neighborhood playground has stopped working.	

 Something is wrong? Correct it

By continuing, you confirm the citizen-provided facts. Automated routing may still be corrected by an assigned official.

Confirm & file complaint

New Complaint : Step-4/Submission Page